

\$7.00
\$2.00

MAY 22 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located in: Solon Twp.
Corner Code # J-11

1. Public Land Survey T10N R 11W
T R
T R
T R

2. Property Controlling in Section S T R
S T R
S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

REG. OF DEEDS

11101
Register of Deeds Stamp & File Number

Kirk Breitels, in a field survey on Jan. 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/11/99
CHAIRMAN *Harry Kubes*

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | |
|-----------|---------------|------------|--------------------------------------|
| J-11 1837 | GLO | Cathcart | Set Post |
| 1966 | Kent Co. Wits | | Conc. Mon. & Iron |
| 1982 | LCRC #3077 | Merdzinski | 1" Iron in Mon. Box |
| 1983 | LCRC #3369 | Bueche | Set Kent County Monument in Mon. Box |
| 1990 | LCRC #5583 | Marschall | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 4-1-83 and was recorded per LCRC #3369.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- J-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" Rebar over a Conc. Mon. he found inside a Mon. Box. Both check with Kent Co. Wit. and LCRC #3077.
- LCRC #3369
- | | | | | |
|-------------------------------|---------------|--------------------------------|---------------|-------------------------|
| Nail & Remon. tag P. Pole | S70°W 86.26' | Nail & Remon. tag P. P. | N70°W 108.85' | Nail & Remon. tag P. P. |
| Nail & MDSH tag P. Pole | N65°W 105.74' | SE corner building #3565 | N35°W 119.38' | P. P. |
| NW cor. frame house | S45°W 100.48' | Conc. R/W marker (face) | N00°E 40.73' | S70°W 86.19' |
| PK Nail 36" Chestnut | S35°W 59.72' | Nail & Remon. tag P. P. | N65°E 83.61' | |
| NW cor. conc. hwy. R/W marker | S40°E 79.50' | Conc. R/W marker (face) | S40°E 79.49' | |
| S. face conc. hwy. R/W marker | North 40.66' | Nail & Remon. tag 36" Chestnut | S35°W 59.70' | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-11 Standard Kent County Monument
- | | |
|---|---------------|
| Nail & KC Remon. tag S. side P. Pole | N70°W 108.85' |
| SE corner brick building #3565 | N35°W 119.38' |
| Face of conc. R/W marker | N00°E 40.73' |
| Nail & KC Remon. tag S. side P. Pole | N65°E 83.65' |
| NW corner conc. R/W marker | S40°E 79.46' |
| Nail & KC Remon. tag W. side 38" Chestnut | S35°W 59.73' |
| Nail & KC Remon. tag S. side P. Pole | S70°W 86.21' |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/25/99