

MAY 22 2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T10N R 11W

Solon Twp.
K-3

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

11103

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-3 1837	GLO	Cathcart	Set Post
	Kent Co. Wits		Stone & Iron
1983	LCRC #3564	VanKooten	Set 1/2" Capped Iron
1992	LCRC #6594	Bueche	Set Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/25/99

CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6594.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Iron he found. Said Iron checks with LCRC #3564 and old measurements. No Kent Co. Wit. remain.
LCRC #6594

Nail & Remon. tag E. side 12" Elm	N10°W	89.15'
Nail & Remon. tag SE side 12" Maple	N45°E	57.56'
Nail & Remon. tag N. side 6" Oak	S80°E	113.52'
Nail & Remon. tag W. side 26" Poplar	S10°E	203.48'
C/L bit. N-S East, 4' ±		
C/L gravel E, South 3' ±		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Standard Kent County Monument

Nail & KC Remon. tag E. side 15" Elm	N10°W	88.97'
Nail & KC Remon. tag SE side 14" Maple	N45°E	57.51'
Nail & KC Remon. tag N. side 8" Oak	S80°E	113.52'
Nail & KC Remon. tag W. side 30" Poplar	S10°E	203.48'
C/L bit. road N-S is East 4' ±		
C/L gravel road East is South 3' ±		

Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 2/25/99

