

MAY 28 2000

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey

T 10 N R 11 W

K-4

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1999 JUL -9 AM 11:19
 RECEIVED FOR RECORD
 STATE OF MICHIGAN
 COUNTY OF KENT
 REGISTER OF DEEDS
 11241
 Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on May 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4	1837	GLO	Cathcart	Set Post
	1977	LCRC #1119	Nederveld	"T" Iron
	1980	LCRC #1304	Hackbardt	"T" Iron
	1981	LCRC #2134	Jonker	Set Kent County Monument
	1990	LCRC #5616	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 6/24/99
 CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9-25-81 and was recorded per LCRC #2134.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron he found. Said "T" Iron checks with LCRC's #1119 & #1304.

LCRC #2134		LCRC #5616	
Nail & Remon. tag 14" Tw. Cherry	S42°E 32.55'	Nail & Remon. tag 20" Ash	N53°E 44.31'
Nail & Remon. tag T. Pole	N27°E 63.92'	Iron in Mon. Box	North 10.04'
Nail & Remon. tag 15" Ash	N57°E 44.40'	Nail & Remon. tag T. Pole	N85°W 81.62'
Nail & Remon. tag P. Pole	N87°W 81.65'	Nail & Remon. tag 18" Tw. Cherry	S42°E 32.54'
Iron in Mon. Box	North 10.03'	Nail & Remon. tag 10" Cherry	S65°E 45.36'
		Nail & Remon. tag T. Pole	N25°E 63.88'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4	Standard Kent County Monument		
	Nail & KC Remon. tag NW side 24" Ash	N53°E	44.33'
	Nail & KC Remon. tag W. side T. Pole	N25°E	63.88'
	Nail & KC Remon. tag S. side P. Pole	N85°W	81.65'
	Nail & KC Remon. tag S. side Tw. 12" Cherry	S65°E	45.41'



Signed by [Signature]
 Surveyor's Michigan License No. 30077

Date 6/24/99