

\$7.00  
\$2.00

MAY 22 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

Solon Twp.  
K-6

1. Public Land Survey

T 10N R 11W

T R

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REG. OF DEEDS

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 JUL -9 AM 11:19

11242

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on May 3, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-6 1837	GLO	Cathcart	Set Post
1967	Kent Co. Wits		Mon. Box
1974	LCRC #658	Spicer	3/4" Iron in Mon. Box
1981	LCRC #2173	Jonker	Set Kent County Monument in Mon. Box
1990	LCRC #5587	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/24/99  
CHAIRMAN Hans Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2173.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron inside a 1 1/2" Iron he found inside a Mon. Box. Both Irons check with Kent Co. Wits. and LCRC #658.	
LCRC #2173	LCRC #5587
NW corner church	S33°E 84.90' Nail & Remon. tag 42" Maple S75°W 113.95'
Nail & Remon. tag T. Pole	N20°E 97.04' Nail & Remon. tag 34" Maple S25°W 60.53'
Nail & Remon. tag 34" Maple	S68°W 75.79' Nail & Remon. tag 6' Maple S23°E 151.65'
Nail & Remon. tag 30" Maple	S30°W 60.57' Nail & Remon. tag 24" Maple S66°E 84.47'
Nail & MSHD tag T. Pole	S18°E 67.95'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Standard Kent County Monument	
Nail & KC Remon. tag W. side 36" Maple	S23°E 151.45'
Nail & KC Remon. tag N. side 27" Maple	S66°E 84.44'
Nail & KC Remon. tag N. side P. Pole	S70°W 143.83'
SW corner conc. porch cap	N50°E 67.53'
Cut Nail S. side 27" Maple	N75°E 118.32'



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 6/24/99