

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| KENT COUNTY (County) | Located In: | Corner Code # |
|------------------------------------|--|---------------|
| 1. Public Land Survey | T <u>10</u> N R <u>11</u> W | <u>K-8</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

REG. OF DEEDS

1999 JUL -9 AM 11:19

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11244

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on May 10, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|----------|---------------|-----------|--------------------------|
| K-8 1837 | GLO | Cathcart | Set Post |
| 1966 | Kent Co. Wits | | 3/4" Pipe |
| 1976 | LCRC #953 | Bonnema | 3/4" Pipe |
| 1981 | LCRC #2169 | Jonker | Set Kent County Monument |
| 1990 | LCRC #5589 | Marschall | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/24/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-6-81 and was recorded per LCRC #2169.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron over a 1 1/2" Pipe he found. Both Irons check with LCRC #953. Kent Co. Wits. are gone.

| LCRC #2169 | | LCRC #5589 | |
|---------------------------------|--------------|---------------------------------|--------------|
| Nail & Remon. tag fence post | N90°E 32.48' | Nail & Remon. tag fence post | N90°E 32.58' |
| Nail & Remon. tag KOA sign post | S30°E 66.86' | Nail & Remon. tag 12" Pine | S70°E 60.79' |
| Nail & Remon. tag 9" Elm | N41°W 84.44' | Nail & Remon. tag KOA sign post | S35°E 66.79' |
| Nail & Remon. tag 6" Pine | S66°E 60.80' | Nail & MSHD tag in post | N15°E 70.34' |

C/L.B.T. is West 2' - C/L grav. West is 8' North

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Standard Kent County Monument

| | |
|---|--------------|
| Nail & KC Remon. tag N. side fence post | N90°E 32.58' |
| Nail & KC Remon. tag S. side 14" Pine | S70°E 60.79' |
| PK Nail W. side "Duke Creek" sign post | S35°E 67.14' |
| Nail & MSHD tag in post | N15°E 70.43' |
| Nail & KC Remon. tag NE side 14" Elm | N45°W 71.20' |



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 6/24/99