

\$7.00
\$2.00

JAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 NOV - 4 AM 8:35

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey

T10N R 11W

K-11

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REG. OF DEEDS

[Signature]

11474

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 27, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|-----------|---------------|-----------|--------------------------------------|
| K-11 1837 | GLO | Cathcart | Set Post |
| 1966 | Kent Co. Wits | | Conc. Mon. & "T" Iron |
| 1972 | LCRC #215 | Spicer | Found PK - Set "T" Iron |
| 198 | LCRC #2180 | Jonker | Set Kent County Monument in Mon. Box |
| 1990 | LCRC #5590 | Marschall | Kent County Monument |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/23/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2180.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron he found inside a Mon. Box. Said "T" Iron checks with LCRC #215 and Kent Co. Wits.

LCRC #2180	Nail & Remon. tag P. Pole	N33°E 89.70'	LCRC #5590	Nail & highway tag Guy Pole	N39°W 58.68'
	Nail & Remon. tag P. Pole	S38°E 59.26'		Nail & Remon. tag P. Pole	N31°E 89.69'
	Nail & Remon. tag Guy Pole	N38°W 58.67'		Nail & Remon. tag P. Pole	N14°E 175.08'
	NE cor. conc. slab of util. ped.	S40°W 70.70'		Nail & highway tag P. Pole	S40°E 59.27'
				Nail & Remon. tag P. Pole	N65°E 161.52'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|-------|---------|
| K-11 Standard Kent County Monument | | |
| Nail & MSHD tag E. side Guy Pole | N39°W | 58.65' |
| Nail & KC Remon. tag NW side P. Pole | N31°E | 89.72' |
| Nail & KC Remon. tag W. side P. Pole | N14°E | 175.06' |
| Nail & MSHD tag NE side P. Pole | S40°E | 59.37' |
| Nail & KC Remon. tag NW side walk signal pole | S40°W | 68.86' |



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 10/28/99