

\$7.00  
\$2.00

MAR 24 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located in:	Corner Code #
T10N R 11W	Solon Twp. K-12
T___ R___	_____
T___ R___	_____
T___ R___	_____
T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:00

11106

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-12 1837	GLO	Cathcart	Set Post
1966	Kent Co. Wits		Iron
1972	LCRC #215	Spicer	1 1/2" Iron
1972	LCRC #297	VanKooten	2" Iron
1981	LCRC #2179	Jonker	Set Kent County Monument
1990	LCRC #5618	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2179.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Round Iron he found. Said Iron checks with Kent Co. Wits. and LCRC's #215 & #279.

LCRC #2179	Nail & Remon. tag 34" Maple N75°W 33.73'	LCRC #5618	Nail & Remon. tag 40" Maple N75°W 33.43'
	Nail & Remon. tag 34" Maple N25°W 64.43'		Nail & Remon. tag 38" Maple N25°W 64.05'
	Nail & Remon. tag 12" Oak S42°W 68.50'		Nail & Remon. tag 14" Oak S42°W 68.57'
	Nail & Remon. tag P. Pole S87°E 75.13'		Nail & Remon. tag P. P. S85°E 75.13'
	Iron West 33.03'		

C/L B.T. is 1' West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Standard Kent County Monument

Nail & KC Remon. tag N. side 40" Maple	N75°W 33.43'
Nail & KC Remon. tag SW side 40" Maple	N25°W 64.05'
Nail & KC Remon. tag E. side 16" Oak	S42°W 68.60'
Nail & KC Remon. tag N. side P. Pole	S85°E 75.13'



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/25/99