

MAY 22 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00  
\$2.00

SECTION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:00

REG. OF DEEDS

11107

Register of Deeds Stamp & File Number

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey

T10N R 11W

Solon Twp.  
L-3

T R

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-3 1837 GLO Cathcart Set Post
- 1875 Williams & Works Found stake
- 1901 Williams & Works Found Iron Pipe
- 1981 LCRC #3564 VanKooten 1 1/2" Iron
- 1992 LCRC #6597 Bueche Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6597.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1 1/2" Iron he found. Said Iron checks with LCRC #3564 and Williams & Works information.  
LCRC #6597

- Nail & KC Remon. tag E. side P. Pole N10°E 31.00'
- Nail & KC Remon. tag S. side 14" Cherry N70°W 72.77'
- Nail & KC Remon. tag S. side 14" Cherry N80°W 113.93'
- Nail & KC Remon. tag S. side tree N85°W 149.18'
- Nail & KC Remon. tag N. side P. Pole S80°W 196.92'

On C/L gravel E-W, C/L drive South is West 33' ±  
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-3 Standard Kent County Monument
- Nail & KC Remon. tag E. side P. Pole N10°E 31.00'
- Nail & KC Remon. tag S. side 16" Cherry N70°W 72.79'
- Nail & KC Remon. tag S. side 16" Cherry N80°W 113.88'
- Nail & KC Remon. tag S. side 30" Maple N85°W 149.13'
- Nail & KC Remon. tag N. side P. Pole S80°W 196.92'
- Iron Pipe S00°W 32.78'

On C/L E-W gravel road  
Gravel drive to South is West 33' ±  
On fence line to South

Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/25/99

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN Harry Tuberville

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

