

LCR 2 & 2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

REG. OF DEEDS
[Signature]

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey

T10N R 11W

L-5

T___ R___

T___ R___

T___ R___

T___ R___

2. Property Controlling
in Section

S___

T___ R___

S___

T___ R___

3. Miscellaneous
Property in Sec.

S___

T___ R___

S___

T___ R___

11108

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-5	1837	GLO	Cathcart	Set Post
	1966	Kent Co. Wits		Iron
	1984	LCRC #3797	Kolehouse	Set Kent County Monument in Mon. Box
	1990	LCRC #5591	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Randy Kolehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 3-30-84 and was recorded per LCRC #3797.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

L-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits.

LCRC #3797		LCRC #5591
Nail & Remon. tag P. Pole	S05°W 54.20'	Nail & Remon. tag P. P. N15°E 40.87'
Nail & Remon. tag P. Pole	N60°W 70.43'	Nail & Remon. tag P. P. N60°W 70.35'
Nail & Remon. tag P. Pole	N15°E 40.87'	Nail & Remon. tag P. P. S05°W 54.13'
NW corner house foundation	S40°E 91.4'	NW cor. house foundation S40°E 91.38'
C/L 20 Mile Rd. is 1' North		
Tree line running South is 2' East		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 Standard Kent County Monument	
Nail & KC Remon. tag W. side P. Pole	N15°E 40.89'
Nail & KC Remon. tag N. side P. Pole	N60°W 70.40'
Nail & KC Remon. tag W. side P. Pole	S05°W 54.17'
NW corner house foundation	S40°E 91.40'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/25/99