

MAY 22 2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 10N R 11W	Solon Twp. L-8
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-8 1837	GLO	Not Set
1903	Williams & Works	Found Oak Stake
1953	Williams & Works	Found Iron at fence corner
1966	Kent Co. Wits	3/4" Pipe
	32" Elm NW 12.47' Fe. Cor. N 4.87'	
1978	LCRC #1214 Bonnema	3/4" Iron
	Spike in 10" Pine S'y 78.79' Spike in Tw. 10" Cherry E'y 51.70' C/L S. Bd. lane US 131 WNW 148.15'	

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 8/26/99
 CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-8 Found 3/4" Iron Pipe in median of US 131 that per remaining witnesses:
 C/L 15" Pine S10°W 79' Fd. Spike in N. side 15" Cherry N90°E 51.71'
 C/L S. Bd. lane US 131 N80°W 148.15'

Said 3/4" Iron Pipe is 1.4 N' and 17.3' W. from intersection of 1/4 lines and has been used in surveys by MSHD, Exxel, and Hackbardt.

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-8 Set Standard Kent County Monument in place of the 3/4" Iron Pipe.
 Nail & KC Remon. tag N. side 15" Cherry N90°E 51.71'
 Nail & KC Remon. tag NE side 6" Pine S25°E 76.14'
 Nail & KC Remon. tag W. side 15" Pine S10°W 78.86'
 C/L S. bound lane US 131 N80°W 148.15'



Signed by [Signature]
 Surveyor's Michigan License No. 30077

Date 10/28/99

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 1999 NOV -4 AM 8:36

11479

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													