

MAY 22 2000

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

REG. OF DEEDS

11109

Register of Deeds Stamp & File Number

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T10N R 11W	Solon Twp. L-9
T___ R___	_____
T___ R___	_____
T___ R___	_____
T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-9 1837	GLO	Cathcart	Set Post
1966	Kent Co. Wits		1/2" Iron
1978	LCRC #1214	Bonnema	1/2" Iron
1981	LCRC #2172	Jonker	Set Kent County Monument
1990	LCRC #5621	Marschall	Kent County Monument

P.A. 345 1900 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Harry Tuben

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2172.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Iron he found. Said Iron checks with LCRC #1214 and Kent Co. Wits.	
LCRC #2172	LCRC #5621
Nail & Remon. tag 8" Oak S34°W 5.90'	Nail & Remon. tag 12" Oak S34°W 6.00'
Nail & Remon. tag 8" Cherry N40°E 19.95'	Nail & Remon. tag 6"-10" Tw. Poplar S82°E 14.09'
Nail & Remon. tag 6" Tw. Poplar S82°E 14.11'	Nail & Remon. tag 24" Cherry S02°E 56.96'
Nail & Remon. tag 20" Cherry S02°E 57.00'	Nail & Remon. tag 6" Cherry N35°W 19.99'
4 way fence corner is NE 4' m/l	N-S fence is E. 4.5' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Standard Kent County Monument	
Nail & KC Remon. tag W. side 18" Oak S34°W 6.00'	
Nail & KC Remon. tag W. side 26" Cherry S02°E 56.96'	
Nail & KC Remon. tag W. side 6" Cherry N35°W 19.99'	
Nail & KC Remon. tag S. side 12" Poplar N85°E 2.75'	
Older N-S fence is East 4.5' ±	
Newer N-S fence is East 1' ±	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/25/99