

\$7.00
\$2.00

MAY 28 2003

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T ¹⁰ N R 11W	Solon Twp. L-11
T___ R___	_____
T___ R___	_____
T___ R___	_____
T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

1999 MAR 24 AM 8:00

11110
Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-11 1837	GLO	Cathcart	Set Post
1966	Kent Co. Wits		Iron Pipe
1974	LCRC #747	D. Hooth	Boat Spike in 1 1/2" Iron Pipe in Mon. Box
1978	LCRC #1207	Jonker	Iron in Mon. Box
1981	LCRC #2170	Jonker	Set Kent County Monument in Mon. Box
1990	LCRC #5622	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2170.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found Kent County Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Capped Copper Rod he found in a Mon. Box. Said Copper Rod checks with LCRC's #747 & #1207 and Kent Co. Wit. LCRC #2170	LCRC #5622
C/L manhole S60°W 27.80'	Nail & Remon. tag P. Pole S40°W 38.00'
C/L manhole S11°E 43.50'	Nail & Hwy. Dept. tag P. Pole N37°W 43.42'
C/L manhole N24°W 13.67'	Center Nut Hydr. N58°E 63.39'
C/L top hydrant N64°E 63.41'	Nail & Remon. tag P. Pole N70°E 106.73'
NW cor. hse. fnd. S34°E 103.03'	NW cor. hse. foundation S34°E 103.00'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag SW side new P. Pole	N37°W 41.32'
Center top nut fire hydrant	N58°E 63.39'
Nail & KC Remon. tag S. side P. Pole	N70°E 106.73'
NW corner house foundation	S34°E 103.05'
C/L manhole	S10°E 34.40'
C/L manhole	S65°W 55.30'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/25/99