

\$7.00  
\$2.00

MAY 28 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	<u>M-1 Solon Twp.</u>
	T <u>   </u> R <u>   </u>	<u>Common</u>
	<del>T <u>10N</u> R <u>10W</u></del>	<del><u>A-1 Nelson Twp.</u></del>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

REG. OF DEEDS  
 STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 1999 JUL -9 AM 11:19

11246

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on May 12, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-1 1837	GLO	Brookfield	Set Post
1937	Kent Co. Wits		Axle
1981	LCRC #2283	Hackbardt	Mon. Box
1985	LCRC #4390	Ochs	Set Kent County Monument on Twp. Line 3.09' South of Mon. Box
1990	LCRC #5592	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 6/24/99  
 CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 10-23-85 and was recorded per LCRC #4390.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Norman L. Ochs on the Twp. line.			
3/4" Iron in Mon. Box per Kent Co. Wits. and LCRC #2283 was 3.09' North of Twp. line.			
LCRC #4390		LCRC #5592	
Tel. Riser	S45°W 54.77'	"X" cut in curb	S45°E 40.04'
Spike in 3" Elm	N45°W 42.52'	"X" cut in curb	S45°W 30.16'
Nail & Remon. tag Tri. Basswood	N60°W 78.92'	Nail & Remon. tag 6" Elm	N40°W 42.48'
Tel. Riser	S45°E 54.88'	Nail & Remon. tag 20" Basswood	N60°W 78.63'
S 1/4 cor. Sec. 31 Pierson Twp.	West 84.67'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 Standard Kent County Monument	
"X" cut in concrete curb	S45°E 40.10'
"X" cut in concrete curb	S45°W 39.16'
Nail & KC Remon. tag W. side dead 6" Elm	N40°W 42.48'
Nail & KC Remon. tag W. side 24" Basswood	N60°W 78.94'
South face of West leg to sign	S05°E 26.08'
1" Iron Pipe at S 1/4 corner, Sec. 31, Pierson Twp.	West 84.69'



Signed by Kirk Breitels  
 Surveyor's Michigan License No. 30077

Date 6/24/99