

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 9:00

REG. OF DEEDS
[Signature]

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R 11W M-5 Solon Twp.
 ~~T10N R 10W~~ ~~A-5 Nelson Twp.~~
 T ___ R ___ _____
 T ___ R ___ _____
- 2. Property Controlling S ___ T ___ R ___ _____
 in Section S ___ T ___ R ___ _____
- 3. Miscellaneous S ___ T ___ R ___ _____
 Property in Sec. S ___ T ___ R ___ _____

11114

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 12, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-5 1836	GLO	Brookfield	Set Post
1967	Kent Co. Wits		3/4" Pipe in Mon. Box
1981	LCRC #2077	Nederveld	7/8" Iron in Mon. Box
1984	LCRC #3793	Kolehouse	Set Kent County Monument in Mon. Box
1990	LCRC #5594	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 3-30-84 and was recorded per LCRC #3793.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #2077.

LCRC #3793	Chiseled "X" N. end 24" culv.	N60°W 68.35'	"X" cut S. end culv. S60°W 68.03'
	Chiseled "X" S. end 24" culv.	S60°W 68.05'	"X" cut N. end culv. N60°W 68.36'
	Nail & Remon. tag 1' dia. wood post	N45°E 53.43'	Nail & Remon. tag 1' post N45°E 53.37'
	Nail & Remon. tag 1' dia. wood post	S45°E 50.90'	Nail & Remon. tag 1' post S45°E 50.84'
	@ C/L 20 Mile Rd. & Cedar Springs Ave.		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Standard Kent County Monument	
"X" cut on S. end culvert	S60°W 68.07'
"X" cut on N. end culvert	N60°W 68.36'
Nail & KC Remon. tag NW side 1' dia. wood post	N45°E 53.43'
Nail & KC Remon. tag NE side 1' dia. wood post	S45°E 50.93'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/25/99