

MAY 22 2000

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:10

REG. OFFICERS

11115

Register of Deeds Stamp & File Number

For corners in:

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T10N R 11W

M-6 Solon Twp.

~~T10N R 10W~~

~~A-6 Nelson Twp.~~

T R

T R

2. Property Controlling
in Section

S T

T R

S T

T R

3. Miscellaneous
Property in Sec.

S T

T R

S T

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 12, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|----------|---------------|------------|--------------------------------------|
| M-6 1836 | GLO | Brookfield | Set Post |
| 1938 | Kent Co. Wits | | 1" Iron & Stone |
| 1980 | LCRC #1416 | Hackbardt | Mon. Box |
| 1981 | LCRC #2077 | Nederveld | 3"4 Iron in Mon. Box |
| 1992 | LCRC #6599 | Bucche | Set Kent County Monument in Mon. Box |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN James Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bucche on 10-12-92 and was recorded per LCRC #6599.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bucche in place of the 3/4" Iron Pipe he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #1416 & #2077 LCRC #6599

| | | |
|----------------------------------|-------|---------|
| "X" cut on top CMP | N10°E | 107.12' |
| "X" cut on top CMP | N10°W | 108.49' |
| Nail & Remon. tag SW side 8" Ash | S60°E | 82.96' |
| Nail W. side P. Pole | S15°E | 119.12' |
| NW cor. conc. pad MBT box | | 118.81' |

On C/L bit. N-S, on C/L gravel East

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|--------------------------------------|-------|---------|
| M-6 Standard Kent County Monument | | |
| "X" cut on top CMP | N10°E | 107.12' |
| "X" cut on top CMP | N10°W | 108.49' |
| Nail & Remon. tag S. side 12" Ash | S70°E | 104.30' |
| Nail & KC Remon. tag SW side 10" Ash | S60°E | 82.96' |
| Nail W. side P. Pole | S15°E | 118.95' |
| NW corner of pad for Ameriteck Box | S25°E | 118.81' |



Signed by Kirk Breitels

Date 2/25/99

Surveyor's Michigan License No. 30077