

\$7.00
\$2.00

MAY 22 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 21 AM 8:00
REG. OF DEEDS

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	<u>M-10 Solon Twp.</u>
	T <u> </u> R <u> </u>	<u>Common</u>
2. Property Controlling in Section	T <u>10N</u> R <u>10W</u>	<u>A-10 Nelson Twp.</u>
3. Miscellaneous Property in Sec.	T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims <u> </u>		

11117
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 9, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10 1837 GLO	Brookfield	Set Post
Kent Co. Wits		PK & "X" cut in pavement
1973 LCRC #489	Spicer	PK Nail
1973 LCRC #561	VanKooten	PK Nail
1982 LCRC #2845	Jonker	Set Kent County Monument
1990 LCRC #5623	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 4-30-82 and was recorded per LCRC #2845.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the PK Nail he found. Said PK Nail checks with Kent Co. Wits. and LCRC's #489 & #561.

LCRC #2845	NE corner frame bldg.	S50°W 73.12'	NW corner 20" x 20" conc. sign base	S30°W 50.13'
	SW corner sign foundation	N45°W 38.17'	Top Hydrant	N55°W 41.30'
	NW corner bldg. (new brick)	S50°E 53.92'	NW corner building	S50°E 53.87'
	Vertical joint on S. face bldg.	N50°E 59.20'	Vertical joint on S. face bldg.	N50°E 59.20'
	Nail & Remon. tag T. Pole	N30°E 46.97'	Nail & Remon. tag T.P.	N30°E 46.90'
	C/L Manhole	S75°W 26.68'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Standard Kent County Monument		
NW corner 20" x 20" concrete sign base	S30°W	50.19'
Top C/L hydrant	N55°W	41.30'
NW corner building	S50°E	53.90'
Vertical joint on S. face building (brick)	N50°E	59.20'
Nail & KC Remon. tag NW side Tel. Pole	N30°E	46.90'
On C/L N-S pavement ±		



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99