

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T10N R 11W

M-11 Solon Twp.

T R

Common

~~T10N R 10W~~

~~A-11 Nelson Twp.~~

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 1837	GLO	Brookfield	Set Post
1939	Kent Co. Wits		Iron in Mon. Box
1971	LCRC #86	Spicer	1" Iron in Mon. Box
1978	LCRC #1207	Jonker	Iron in Mon. Box
1981	LCRC #2007	Jonker	Set Kent County Monument in Mon. Box
1990	LCRC #5598	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8-20-81 and was recorded per LCRC #2007.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Iron he found in a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #86 & #1207.

LCRC #2007		LCRC #5598
SE corner bldg. (corner stone)	N43°W 53.63'	Nail & Remon. tag Guy Pole S15°E 100.91'
C/L Hydrant	S53°W 53.92'	Top Hydrant S50°W 54.07'
C/L Manhole	West 18.04'	SE corner building stone ledge N45°W 53.62'
C/L Manhole	East 17.83'	Nail & MDOT tag Guy Pole N25°E 56.70'
C/L Manhole	N38°E 24.76'	Nail & Remon. tag U.P. N75°E 99.25'
C/L Manhole	S18°W 49.44'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag W. side Guy Pole	S15°E 100.79'
C/L top of fire hydrant	S50°W 54.00'
SE corner building stone ledge	N45°W 53.66
Nail & MDOT tag E. side Guy Pole	N25°E 56.70'
Nail & KC Remon. tag N. side Util. Pole	N75°E 99.27'
NW corner sign base	S55°E 65.33'
At C/L intersection ±	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99

REG. OF NEEDS

1999 MAR 21 AM 8:00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11118

Register of Deeds Stamp & File Number