

SURVEY & REMONUMENTATION

MAY 09 1996

other

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970 **3 AUG 24 PM 2:53**

For corners in

Kent. (County)	Located In:	Corner Code //
1. Public Land Survey	T 10N R 11W	South witness monument to J-3
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<i>Other Code</i>
	S _____ T _____ R _____	<i>#6</i>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REG. OF DEEDS

6808

Register of Deeds Stamp & File Number

I, **Wallace E. Glaza**, in a field survey on **August 12**, 19**93** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration
 No previous history.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 South witness monument to J-3, T10N, R11W, Solon Township, Kent County, Michigan.
 Set standard 4" x 30" Harrison Monument on a straight line between the center of Section 11 and the computed location of J-3, 2550.34' North of the center of Section 11 and 26' South of waters edge of Lower Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 South witness monument to J-3, T10N, R11W, Solon Township, Kent County, Michigan

- 1) Nail and tag in E side 10" Elm N00°E 11.54'
- 2) Nail and tag in NE side 24" Oak S40°E 28.56'
- 3) Nail and tag in W side 24" Oak S20°W 61.73'
- 4) Nail and tag in S side 8" Elm S90°W 7.20'
- 5) Northwest corner house S20°E 99.70'



Signed by *Wallace E. Glaza*
 Glaza and Associates, Inc.
 Surveyor's Michigan License No. 31592

Date **8-17-93**