

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ 25 _____	T. _____ 10 N. _____ 12 E. _____ S. R. _____ W.	M-9, L-9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. R. _____ W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DEC 13 8 57 AM '85
4313
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-9 NE Cor. Iron Spike in 10" double w.ch. - N. NW - 45.82' Spike in 8" double Oak - E. NE - 40.05' Spike in 10" Poplar - S. SE - 29.74' Spike in post (State Game Area) - S. SW - 43.11'	L-9 N½ Cor. Nothing Found Set 4" x 36" conc. mon. M.P.O.L. in s. edge gravel road.
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 NE Cor. Fd. Iron N. NW - 45.82' - Spike in 10" Cherry Clump E. NE - 40.05' - Spike in 8" double Oak S. SE - 29.74' - Spike in 10" Poplar S. SW - 43.11' - Spike in Sign Post.	L-9 N½ Cor. 4" x 36" conc. mon. in s. edge gravel road. N29°E - 36.73' - Spike in 12" triple oak. S77°E - 43.50' - Spike in 18" Oak. S15°W - 35.19' - Spike in 10" Oak. S83°W - 51.99' - Spike in 10" Oak.
--	---


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald Bissell DATE 12-9-85
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655