

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey	T <u>10</u> N R <u>12</u> W	A-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 NOV - 4 AM 8:36

11483

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 20, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-4 1837	GLO	Brookfield	Set Post
1964	Kent Co. Wits		3/4" Iron
1979	LCRC #1315	Nederveld	3/4" Iron in Mon. Box
1983	LCRC #3239	Byl	Set Kent County Monument in Mon. Box
1994	LCRC #7516	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/23/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 3-11-83 and was recorded per LCRC #3239.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


A-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 3/4" Iron Pipe he found in a Mon. Box. Said Iron Pipe checks with Kent Co. Wits. and LCRC #1315.

LCRC #3239	Nail & Remon. tag P. Pole	N20°W	177.05'	LCRC #7516	Nail & Remon. tag P. Pole	N20°W	176.95'
	Nail & Remon. tag P. Pole	N20°E	175.40'		Nail & Remon. tag P. Pole	N20°E	175.27'
	SW corner house foundation	N35°E	202.00'		Drill hole N. end 12" culvert	N50°W	37.16'
	Drill hole N. end 12" culvert	N50°W	37.17'		Cut "X" on S. end 12" culvert	S80°W	37.14'
	Drill hole S. end 12" culvert	S80°W	30.26'		Cut "X" on S. end conc. culvert	N22°E	81.17'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 Standard Kent County Monument			
Nail & KC Remon. tag E. side P. Pole	N20°W	177.04'	
Nail & KC Remon. tag W. side P. Pole	N20°E	175.27'	
Drill hole on N. end 12" concrete culvert	N50°W	37.22'	
"X" cut top S. end concrete culvert	S80°W	37.18'	
"X" cut top S. end concrete culvert	N22°E	81.17'	
Nail & KC Remon. tag N. side 6" Apple	S80°E	68.44'	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 10/20/99