

SURVEY & REMONUMENTATION

MAY 22 2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

[Handwritten Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 NOV -1, AM 8:37

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 12W	Tyrone Twp. A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

11486

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-7 1837	GLO	Brookfield	Set Post
	Kent Co. Wits		Leaded Stone
1981	LCRC #2067	Nederveld	3/4" Round Iron in Mon. Box
1983	LCRC #3242	Byl	Set Kent County Monument in Mon. Box
1994	LCRC #7520	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/23/99
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 3-21-83 and was recorded per LCRC #3242.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 3/4" Iron Pipe under a 1" Iron Pipe he found inside a Mon. Box. Both Irons check with Kent Co. Wit. and LCRC #2067.	LCRC #3242	LCRC #7520	
Nail & Remon. tag P. Pole	N45°W 106.00'	Nail & Remon. tag P. Pole	S15°E 169.25'
Nail & Remon. tag P. Pole	S15°E 169.25'	Nail & Remon. tag P. Pole	N65°E 133.95'
Nail & Remon. tag P. Pole	N65°E 134.08'	Nail & Remon. tag 8" Maple	N62°W 89.27'
Nail & Remon. tag 12" Apple	S55°W 95.25'	PK Nail in crack conc. gutter	S43°W 45.29'
			On C/L N-S and E-W roads

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Standard Kent County Monument	
Nail & KC Remon. tag E. side P. Pole	S15°E 169.22'
Nail & KC Remon. tag N. side P. Pole	N65°E 133.95'
Nail & KC Remon. tag NE side 12" Maple	N62°W 89.35'
PK Nail in crack of concrete gutter	S43°W 45.29'
On C/L roads N-S and E-W ±	



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 10/28/99