

**SURVEY &  
REMONUMENTATION**

MAY 22 2000

\$7.00  
\$2.00

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey

T 10 N R 12 W

A-8

T R

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 NOV -4 AM 8:37

**11487**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Sept. 20, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/23/99  
CHAIRMAN [Signature]

A. Description of original monument and accessories and/or subsequent restoration:

A-8 1837	GLO	Brookfield	Set Post
1958	Kent Co. Wits		2" Iron & Boat Spike
1982	LCRC #3157	Hackbardt	Mon. Box
1983	LCRC #3372	Bueche	Set Kent County Monument in Mon. Box
1994	LCRC #7547	J. Glaza	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 4-25-83 and was recorded per LCRC #3372.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Boat Spike he found in a Mon. Box. Said Boat Spike checks with Kent Co. Wits. and LCRC #3157.

LCRC #3372		LCRC #7547	
Nail & Remon. tag P. Pole	N15°E 101.90'	Nail & Remon. tag P. Pole	N15°E 101.90'
Nail & Remon. tag 12" Maple	N30°W 76.28'	Nail & Remon. tag 18" Twin Maple	N30°W 76.16'
Nail & Remon. tag 18" Beech	N85°W 52.28'	Nail & Remon. tag 48" Beech	N85°W 52.88'
Nail & Remon. tag 18" Maple	S65°W 59.58'	Nail & Remon. tag 26" Maple	S65°W 59.60'
Nail & Remon. tag 16" Walnut	N90°E 56.25'	NW cor. hse. find.	S40°E 74.44'
NW cor. hse. find	S40°E 74.44'	C/L MH	S05°W 58.15'
		C/L Manhole	S05°W 58.15'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag E. side P. Pole	N15°E 101.90'
Nail & KC Remon. tag NE side Twin 18" Maple	N30°W 76.16'
Nail & KC Remon. tag S. side 48" Beech	N55°W 52.79'
Nail & KC Remon. tag N. side 28" Maple	S65°W 59.30'
NW corner house foundation	S40°E 74.44'
C/L Manhole	S05°W 58.20'
Near C/L N-S asphalt road	



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 10/25/99