

\$7.00  
\$2.00

MAY 24 2000

# KENT COUNTY REMONUMENTATION

## SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

Located In:	Corner Code #
	Tyrone Twp.
1. Public Land Survey	T <u>10</u> N R <u>12</u> W
	T <u>   </u> R <u>   </u>
	T <u>   </u> R <u>   </u>
	T <u>   </u> R <u>   </u>
	T <u>   </u> R <u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>

REG. OF DEEDS

1999 JUL -9 AM 11:20

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

11249

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on May 25, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1 1837	GLO	Whitcomb	Set Post
1970	Williams & Works		Set "T" Iron
1973	LCRC #537	Spicer	"T" Iron
1985	LCRC #4370	Ochs	Set Kent County Monument
1994	LCRC #7527	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 6/24/99  
 CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 10-16-85 and was recorded per LCRC #4370.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Norman L. Ochs on Twp. line 2.43' South of "T" Iron per LCRC #537. "T" Iron did check with LCRC #537 and Williams & Works information.

LCRC #4370	LCRC #7527
Chisel mark on S. end culv. SE 52.79'	C/L 6' CMP is 48' East
Chisel mark on N. end culv. NE 53.14'	In C/L E-W gravel road
C/L 6' CMP is East 48'	Chisel mark on top edge of S. end culvert S63°E 52.80'
C/L E-W gravel road is South 3'	Chisel mark on top edge of N. end culvert N65°E 53.09'
	Rerod S10°E 53.28' Rerod N44°W 50.41'
	Newaygo Co. Mon. (S 1/4 cor. 32-11-12) N90°E 268.91'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Standard Kent County Monument\*

Chisel mark on top edge of S. end culvert	S63°E	52.80'
Chisel mark on top edge of N. end culvert	N65°E	53.09'
Rerod	S10°E	53.33'
Rerod	N44°W	50.38'
Newaygo Co. Mon. (S 1/4 cor. 32-11-12)	N90°E	268.88'



Signed by *[Signature]*  
 Surveyor's Michigan License No. 30077

Date 6/24/99