

\$7.00  
\$2.00  
MAY 22 2000  
SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |                           |                    |
|---------------------------------------|---------------------------|--------------------|
| <u>KENT COUNTY</u><br>(County)        | Located In:               | Corner Code #      |
| 1. Public Land Survey                 | T <u>10N</u> R <u>12W</u> | Tyrone Twp.<br>C-4 |
|                                       | T ___ R ___               | _____              |
|                                       | T ___ R ___               | _____              |
|                                       | T ___ R ___               | _____              |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___         | _____              |
|                                       | S ___ T ___ R ___         | _____              |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___         | _____              |
|                                       | S ___ T ___ R ___         | _____              |
| 4. Lot No. _____, Recorded Plat _____ |                           |                    |
| 5. Private Claims _____               |                           |                    |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 NOV -4 AM 8:37  
REG. OF DEEDS

11491

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Sept. 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |    |   |   |   |   |   |
|----|----|----|----|----|----|----|----|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H  | I | J | K | L | M |
| 1  |    |    |    |    |    |    |    |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |    |   |   |   |   |   |
| 3  |    |    |    |    |    |    |    |   |   |   |   |   |
| 4  | 7  | ●  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |
| 5  |    |    |    |    |    |    |    |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |    |   |   |   |   |   |
| 7  |    |    |    |    |    |    |    |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |    |   |   |   |   |   |
| 9  |    |    |    |    |    |    |    |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |    |   |   |   |   |   |
| 11 |    |    |    |    |    |    |    |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |    |   |   |   |   |   |
| 13 |    |    |    |    |    |    |    |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

|     |      |            |           |                          |
|-----|------|------------|-----------|--------------------------|
| C-4 | 1837 | GLO        | Whitcomb  | Set Post                 |
|     | 1984 | LCRC #3881 | Kolehouse | Set Kent County Monument |
|     | 1994 | LCRC #7553 | J. Glaza  | Kent County Monument     |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 9/23/99  
CHAIRMAN Randy J. Kolehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 8-11-84 and was recorded per LCRC #3881.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 Found BROKEN Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the Capped Iron (#25344) he found. Said Iron is on line ± with NW & SW corners and on fences E-W. Removed and reset Kent County Monument (Harrison) in Mon. Box.

|                                 |              |                                  |              |
|---------------------------------|--------------|----------------------------------|--------------|
| LCRC #3881                      | LCRC #7553   |                                  |              |
| Nail & Remon. tag 8" Elm        | N50°W 43.82' | Nail & Remon. tag 13" Tw. Willow | N30°E 47.00' |
| Nail & Remon. tag 8" Tw. Willow | N30°E 47.03' | Nail & Remon. tag 12" Poplar     | N75°E 23.83' |
| Nail & Remon. tag 8" Poplar     | N75°E 23.90' | Chiseled "X" top conc. culv.     | S50°E 26.37' |
| Chiseled "X" top conc. culv.    | S50°E 26.45' | Nail & Remon. tag 12" Elm        | N44°W 43.80' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 Standard Kent County Monument in Mon. Box

|   |              |
|---|--------------|
| Nail & KC Remon. tag SW side Tw. 18" Willow | N30°E 47.02' |
| Nail & KC Remon. tag N. side 12" Poplar     | N75°E 23.83' |
| Chiseled "X" top concrete driveway culvert  | S50°E 26.37' |
| Nail & KC Remon. tag N. side P. Pole        | N85°W 33.03' |
| Nail & KC Remon. tag                        |              |



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 10/28/99