


0000 88 YAR

## KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

I OF COURSE III		1	•	r	<u>( -                                   </u>	N		$\Box$	
KENT COUNTY	Located In:	Corner Code #				÷.	- FO	T4:	
(County)				7		70x	- 25 TN - 27 ZK	$\subseteq$	
1. Public Land Survey	T <u>10N</u> R <u>1</u> T R T R	Tyrone Twp.  2W C-7	;	7		<u></u>	CONT.	S.Z.	
Property Controlling     in Section     Miscellaneous	TR_ S TR_ S TR_ S TR			11	133	3			
Property in Sec.	srR		Regis	ter of [	Deeds	Stamp	& File	Num	ber
4. Lot No, Reco	rded Plat		•						
5. Private Claims	recorrac		A B	C D	E F	G H	I J	J K	L
			z 6-	 	4-	_ <del> </del>		<u> </u> 	<u> </u> <u> </u>
Kirk Breitels	in a field survey on	Jan. 15 , 19 99 do hereby state that und	3		+	+	+		
requirements of P.A. 74, Michlg	an P.A. of 1970, the corner	points mentioned in lines 1 and 2 above were	in _		]	<b>T</b> i		1	-1 <i>Z</i> -
conformance with regulations an United States Department of the that the corner points mentioned	'or 6	17-	16-	15	1	4	-13-		
Board of Land Surveyors or b recovered, found as expressed b	y a Decree of a Court of	Law; established, re-established, monumente	d, 7 19	20	21	22		3	-24-
			- 1 - 7	1 1	1 1	1 7	1 ~	· 1	ī.



NOTE: Not more than 2 corners, all in the same town and range, may be recorded

on this certificate.

C-7 1837 1981 1982	GLO Kent Co. Wits LCRC #2067 LCRC #3125	Whitcomb  Nederveld  Merdzinski	Set Post Hub on Stone 1" Round Iron in Mon. Box Set Kent County Monument	P.A. 345 1990 KENT COUNTY PEER APPROVED 2/25/99 CHAIRMAN / Long 9 Lubere
1994	LCRC #7581	J. Glaza	Kent County Monument	, , , , , , , , , , , , , , , , , , , ,

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Mcrdzinski on 10-15-82 and was recorded per LCRC #3125.

## Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Concrete Spike he found. Said Concrete Spike checks with Kent Co. Wits. No witnesses per LCRC #2067 remain.

LCRC #3125 LCRC #7581 Nail & Remon. tag P. Pole N20°W 74.63' Nail & Remon. tag P. Pole N20°W 74.63' Nail & Remon. tag 24" Maple S45°W 91.2' Nail & Remon. tag 32" Maple S45°W 91.89' N65°E 145.10' Nail & Remon. tag P. Pole "N65°E 145.10 Nail & Remon. tag P. Pole NW corner base to MBT Box S40°E 68.94' NW corner of base to MBT Box S40°E 68.94' At C/L "X" of roads N-S & E-W At C/L "X" road N-S & E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available

evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Standard Kent County Monument		
Nail & KC Remon, tag E. side P. Pole	N20°W	74.63'
Nail & KC Remon. tag SE side 36" Maple	S45°W	91.89'
Nail & KC Remon. tag N. side P. Pole	N65°E	145.10'
NW corner of base to MBT Box	, S40°E	68.97'

On C/L "X" road N-S & E-W

Surveyor's Michigan License No.

Signed by 30077

2/25/29 Date



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14,1975 REVISED JAN., 1983 REVISED OCT., 1985