

MAY 22 2000

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

[Signature]

1999 MAR 24 AM 8:01

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11136

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

C-10

1. Public Land Survey

T 10N R 12W

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Kirk Breitels, in a field survey on Jan. 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- C-10 1837 GLO Whitcomb Set Post
- 1958 Kent Co. Wits 1" Iron in Mon. Box
- 1971 LCRC #2 Ratekin 1" Iron in Mon. Box
- 1973 LCRC #463 Spicer 2" Iron in Mon. Box
- 1982 LCRC #2643 Jonker Set Kent County Monument in Mon. Box
- 1994 LCRC #7587 J. Glaza Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 2-8-82 and was recorded per LCRC #2643.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 Found Kent County Mon. (Harrison) per witnesses of above LCRC as set by Robert J. Jonker in place of the Square Spike over a 2" Iron he found inside a Mon. Box. Both Irons check with Kent Co. Wits. and LCRC's #2 & #463.

LCRC #2643	Nail & Remon. tag P. Pole S20°W 112.74'	LCRC #7578	Nail & Remon. tag P. Pole S20°W 112.74'
	Nail & Remon. tag guard post S07°E 60.24'		Nail & Remon. tag T. Pole N13°E 97.70'
	Nail & Remon. tag T. Pole N13°E 97.95'		C/L tip conc. R/W marker N85°E 28.60'
	C/L top conc. R/W marker N85°E 28.45'		Nail & Remon. tag 10" Quad Box Elder N80°W 63.75'
	C/L top conc. R/W marker S65°W 45.6'		C/L pavement is 1' West
	C/L pavement 1' West m/l		C/L Ball Creek, 70' ± North

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-10 Standard Kent County Monument in Mon. Box
- Nail & KC Remon. tag E. side P. Pole S20°W 112.64'
- Nail & KC Remon. tag W. side T. Pole N13°E 97.70'
- C/L top concrete project marker N85°E 28.60'
- Nail & KC Remon. tag N. side Tri. 6"-12" Box Elder N80°W 63.75'
- Nail & KC Remon. tag SW side 10" Box Elder S40°E 83.83'
- C/L pavement is 1' West
- C/L Ball Creek is North 70' ±



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 2/25/99