

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 9:01

REG. OF DEEDS
[Signature]

11137

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey	T	10N	R	12W	C-12
	T		R		
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 19, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-12 1837	GLO	Whitcomb	Set Post
1940	Kent Co. Wits		Mon. Box
1975	LCRC #895	Bonnema	3/4" Iron in Mon. Box
1982	LCRC #2644	Jonker	Set Kent County Monument in Mon. Box
1994	LCRC #7556	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 2-10-82 and was recorded per LCRC #2644.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron over a 1 1/2" Iron he found inside a Mon. Box. Both Irons check with Kent Co. Wits. and LCRC #895.	
LCRC #2644	LCRC #7556
Nail & Remon. tag T. Pole S52°E 57.24'	Nail & Remon. tag P. Pole N45°W 65.74'
Nail & Remon. tag P. Pole N45°W 65.74'	Nail & Remon. tag 16" Pine S75°E 107.76'
NE cor. top of conc. porch S47°W 130.09'	Nail & Remon. tag P. Pole S25°W 164.45'
C/L stop sign N60°E 50.7'	Nail & Remon. tag P. Pole N80°E 202.84'
On line C/L gravel road to East	On line C/L bit. road to East
1.8' West of N-S pavement	C/L N-S bit. road is 2' ± East

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Standard Kent County Monument	
Nail & KC Remon. tag SW side P. Pole	N45°W 65.74'
Nail & KC Remon. tag N. side 18" Pine	S75°E 107.76'
Nail & KC Remon. tag E. side P. Pole	S25°W 164.45'
Nail & KC Remon. tag S. side P. Pole	N80°E 202.84'
C/L Top Telephone Box	S50°E 57.18'
On line with C/L asphalt road to East	
C/L N-S asphalt road is 2' ± East	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99