

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 JUL 14 AM 9:55

For corners in
KENT COUNTY

Located in:

Corner Code #

(County)

1. Public Land Survey

T	10N	R	12W	B-13
T		R		
T		R		
T		R		
S		T		
S		T		
S		T		
S		T		

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Luis J. Bond
REG. OF DEEDS

10659

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-13 1837 GLO	Brookfield	Set Post
1940 Kent Co. Wits		Concrete Monument
1977 LCRC #1115	Nederveld	"T" Iron over Concrete Monument
1980 LCRC #1502	Merdzinski	Set Kent County Monument
1994 LCRC #7569	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/25/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 12-9-80 and was recorded per LCRC #1502.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the "T" Iron over concrete Monument he found. Both check with Kent Co. Wits. & LCRC #1115.
LCRC #1502 LCRC #7569

Nail & Remon. tag 10" Pignut	N75°E	78.58'	Nail & Remon. tag 12" Pignut	N75°E	78.60'
Nail & Remon. tag 8" Pignut	N40°E	28.59'	Nail & Remon. tag P. Pole	N28°W	249.91'
Nail & Remon. tag 6" Pignut	N05°W	42.12'	Nail & Remon. tag 10" Pignut	N05°E	26.90'
Nail & Remon. tag P. Pole	S70°E	183.60'	Nail & Remon. tag P. Pole	S75°W	227.99'
"X" on top culvert	S70°W	185.53'	Kent Co. Mon. (N 1/4 cor. 6-9-12)	West	15.18'
"X" on top culvert	N70°W	189.41'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 Standard Kent County Monument		
Nail & KC Remon. tag S. side 12" Pignut	N75°E	78.55'
Nail & KC Remon. tag E. side P. Pole	N28°W	249.95'
Nail & KC Remon. tag 10" Pignut	N05°E	26.90'
Nail & KC Remon. tag N. side P. Pole	S75°W	228.03'
Kent Co. Mon. (B-1, T9N, R12W)	West	15.21'
On C/L E-W asphalt road		
On tree line to North		



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 6/25/98