

**SURVEY & REMONUMENTATION**  
 MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 OCT -7 AM 10:15  
 REG. OF DEEDS  
*Lucy Bond*

**SECTION**  
 For corners in  
 KENT COUNTY  
 (County)

Located In:	Corner Code #
T 10N R 12W	D-13
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

**10706**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Sept. 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13	*												

**A. Description of original monument and accessories and/or subsequent restoration:**

D-13 1837 GLO Brookfield Set Post  
 1993 LCRC #6888 Bueche Set Kent County Monument - no witnesses within 500'

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12-22-93 and was recorded per LCRC#6888.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-13 Found BROKEN Kent County Monument (Harrison) in field, per information from above LCRC as set by John C. Bueche on township line 8.25' West of D-1, T9N, R12W (LCRC #6885) - computations per Roosien.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 9/24/98  
 CHAIRMAN Harry Huber

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-13 Established location of corner per information of LCRC #6885 and LCRC # 6888 - On township line and 8.25' West of D-1, T9N, R12W. Corner falls in soybean field - decided not to set monument here but to refer to witness monuments set for D-1, T9N, R12W.

See LCRC # 10705 & LCRC # 10707 for location of witness monuments.

Signed by Kirk Breitels  
 Surveyor's Michigan License No. 30077

Date 9/24/98

