

\$7.00  
\$2.00

SURVEY &  
RECORDATION

MAY 22 2000

# KENT COUNTY REMONUMENTATION

SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 10 N R 12 W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

Tyrone Twp.  
E-6

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

1999 MAR 24 AM 8:01

REG. OF DEEDS

11147

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 15, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-6 1837	GLO	Whitcomb	Set Post
1938	Kent Co. Wits		Stone & Iron
1981	LCRC #2080	Nederveld	Iron in Mon. Box
1982	LCRC #3011	Starr	Set Kent County Monument in Mon. Box
1994	LCRC #7544	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas C. Starr on 8-2-82 and was recorded per LCRC #3011.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas C. Starr in place of the 1/2" Iron Pipe he found in a Mon. Box. Said Iron Pipe checks with Kent Co. Wit. and LCRC #2080.	
LCRC #3011	LCRC #7544
Nail & Remon. tag P. Pole N85°W 36.81'	Nail & Remon. tag P. Pole N85°W 36.83'
Nail & Remon. tag 8" Pine S75°W 73.05'	Nail & Remon. tag 12" Pine S75°W 72.98'
Nail & Remon. tag P. Pole S20°E 101.95'	Nail & Remon. tag P. Pole S20°E 101.95'
C/L top Bell Undgrd. Box N40°E 64.44'	C/L top Bell Undgrd. Box N36°E 63.20'
NE cor. frame house N60°W 126.23'	NE cor. frame house N60°W 126.23'
NE cor. fnd. house S40°W 141.80'	On C/L N-S bit. road and on fence line West and tree line East

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag N. side P. Pole	N85°W 36.79'
Nail & KC Remon. tag N. side 18" Pine	S75°W 72.93'
Nail & KC Remon. tag W. side P. Pole	S20°E 101.95'
C/L top of Ameritech Underground Box	N36°E 63.16'
NE corner house foundation	N60°W 126.23'
On C/L N-S bit. road	
On fence line West and tree line East ±	



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/25/99