

STATE OF MICHIGAN  
DEPARTMENT OF LAND SURVEY & MAPPING

KENT COUNTY REMONUMENTATION

MAY 28 2008

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00  
\$2.00

SECTION

REG. OF DEEDS

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:11

11151

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY (County)	Located in:	Corner Code #
1. Public Land Survey	T 10N R 12W T R T R T R	Tyrone Twp. E-10
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-10 1837	GLO	Whitcomb	Set Post
1971	Kent Co. Wits		Boat Spike
1973	LCRC #463	Spicer	Boat Spike
1982	LCRC #2711	Jonker	Set Kent County Monument in Mon. Box
1994	LCRC #7577	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN Franz Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 3-10-82 and was recorded per LCRC #2711.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Iron he found inside a Mon. Box. Said Iron checks with LCRC #463 and Kent Co. Wit.  
LCRC #2711

Nail & Remon. tag P. Pole	S70°E 27.45'	Nail & Remon. tag P. Pole	S70°E 27.49'
Nail & Remon. tag 34" Maple	S10°E 128.44'	Nail & Remon. tag 34" Maple	S10°E 128.44'
Nail & Remon. tag 8" Birch	N90°W 68.36'	Nail & Remon. tag 18" Tw. Maple	N25°W 122.76'
Nail & Remon. tag in guard post N30°W 50.53'		Nail & Remon. tag 10" Maple	S70°W 121.51'
C/L pavement is East 3' m/l		C/L E-W pole line is 8' S.	
C/L E-W pole line is 8' South		C/L pavement is East 3' m/l	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 Standard Kent County Monument in Mon. Box	S70°E 27.45'
Nail & KC Remon. tag N. side P. Pole	S10°E 128.41'
Nail & KC Remon. tag W. side 36" Maple	N25°W 122.76'
Nail & KC Remon. tag NE side 18" Twin Maple	S70°W 121.47'
Nail & KC Remon. tag N. side 12" Maple	
C/L E-W pole line is 8' South	
C/L pavement is East 3' ±	



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/25/99