

MAY 24 2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey		T 10N R 12W	Tyrone Twp. E-12
		T R	
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 9:01

11152

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-12 1837	GLO	Whitcomb	Set Post
1960	Kent Co. Wits		3/4" Iron in Conc. Mon.
1971	LCRC #88	Spicer	"T" Iron
1983	LCRC #3426	Bucche	Set Kent County Monument in Mon. Box
1994	LCRC #7555	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 5-17-83 and was recorded per LCRC #3426.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the "T" Iron he found in a Mon. Box. Said "T" Iron checks with Kent Co. Wit. and LCRC #88.

LCRC #3426	LCRC #7555
Nail & Remon. tag P. Pole S50°E 90.96'	Nail & Remon. tag P. Pole S48°E 90.98'
Nail & Remon. tag P. Pole N60°E 71.44'	Nail & Remon. tag P. Pole N60°E 71.50'
"X" cut in conc. curb return S30°E 44.15'	"X" cut in conc. curb return S30°E 44.15'
"X" cut in conc. curb return N35°W 28.70'	"X" cut in conc. curb return N35°W 28.72'
"X" cut in conc. curb return S70°W 42.17'	"X" cut in conc. curb return S70°W 42.16'
C/L M-37 joint S15°W 86.25'	C/L joint M-37 S15°W 86.25'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 Standard Kent County Monument	
Nail & KC Remon. tag NE side P. Pole	S48°E 90.95'
Nail & KC Remon. tag NW side P. Pole	N60°E 71.58'
Top C/L "L" fence post	N40°W 121.75'
Nail & KC Remon. tag E. side Guy Pole	S25°W 123.87'
Cut "X" top concrete curb	N90°W 71.36'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99