

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

MAR 08 1999

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:31

REG. OF DEEDS

Lucy Bond

For corners in SECTION
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T10N R 12W	E-13
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

10506

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 26, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-13 1837 GLO	Brookfield	Set Post
1910 Williams & Works		Witnesses given
1935 Kent Co. Wits		Stone
1958 MSHD		3/4" Steel Rod
1992 LCRC #6613	Bueche	Set Kent County Monument
1994 LCRC #7562	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY,
PEER APPROVED 2/19/98
CHAIRMAN Harry Kuber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC#6613.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" Rod he found. Said 3/4" Rod checks with Williams & Works, Kent Co. Wits. and MSHD.
LCRC #6613 LCRC #7562

Nail & Remon. tag 26" Basswood West	19.21'	Nail & Remon. tag 26" Basswood West	19.19'
Nail & Remon. tag P. Pole	S05°E 62.90'	Nail & Remon. tag P. Pole	S05°E 62.90'
Nail & Remon. tag P. Pole	S70°E 53.25'	Nail & Remon. tag P. Pole	S70°E 53.25'
Nail & Remon. tag P. Pole	N75°E 117.48'	Nail & Remon. tag P. Pole	N75°E 117.48'
Nail & Remon. tag 10" Oak	S05°W 41.47'	Nail & Remon. tag 10" Oak	N05°W 41.47'
Kent Co. Mon. (NE cor. 5-9-12)	East 31.77'	Kent Co. Mon. (NE cor. 5-9-12)	East 31.77'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Standard Kent County Monument

Nail & KC Remon. tag S. side 30" Basswood	West	19.21'
Nail & KC Remon. tag NE side P. Pole	S70°E	53.25'
Nail & KC Remon. tag N. side P. Pole	N75°E	117.48'
Nail & KC Remon. tag E. side Tw. 6" Basswood	N05°W	41.39'
Nail & KC Remon. tag E. side 14" Basswood	S00°E	72.45'
Kent Co. Mon. (E-1, T9N, R12W)	East	31.77'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98