

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 17 AM 8:01

REG. OF DEEDS

[Signature]

11623

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey

T 10NR 12W

F-6

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-6 1837 GLO
1961 Williams & Works
Kent Co. Wits

Not Set
Held computed distance of 2649.83' from N 1/4 corner to C 1/4 corner (on line with E 1/4 corner and W 1/4 corner
No information

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/26/99
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-6 Found Capped Rerod (N & J) that is 0.3' S. and less than 0.1' W. from intersection of 1/4 lines.

Also found Capped Rerod (All Points) that is 0.8' N. and 1.2' E. from intersection of 1/4 lines (1.7' NE of N & J Capped Rerod)

Both Capped Rerods near fence corner N-S & E.

The Capped Rerod (N & J) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-6 Set Standard Kent County Monument in place of the Capped Rerod (N & J)
Nail & KC Remon. tag N. side 10" Oak West 16.19'
Nail & KC Remon. tag W. side 24" Maple N10°E 36.18'
Nail & KC Remon. tag N. side 6" Maple N85°E 18.05'
Nail & KC Remon. tag E. side 24" Oak S05°E 15.50'
4-way fence corner is 1' East and 3' South



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 12/15/99