

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey

T10N R 12W

F-9

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

1999 MAR 24 AM 9:02

REG. OF DEEDS

11155

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M			
1																
2	6			5			4			3			2	1		
3																
4	7						8			9			10	11	12	
5																
6	18									16			15	14	13	
7																
8	19									20			21	22	23	24
9																
10	30									29			28	27	26	25
11																
12	31									32			33	34	35	36
13																

A. Description of original monument and accessories and/or subsequent restoration:

F-9 1837	GLO	Whitcomb	Set Post
1961	Kent Co. Wits		1/2" Iron
1973	LCRC #573	Spicer	1/2" Iron
1982	LCRC #2708	Jonker	Set Kent County Monument
1991	LCRC #5733	Bucche	Reset Kent County Monument
1994	LCRC #7573	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 3-15-82 and was recorded per LCRC #2708.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Iron over a 3/4" Iron in Stones he found. Both Irons check with Kent Co. Wit. and LCRC #573, LCRC #2708 & #7573

Nail & Remon. tag P. Pole	N35°W 63.42'	Nail & Remon. tag P. Pole	N35°W 63.42'
Nail & Remon. tag 24" Oak	S80°W 99.57'	"X" cut in curb	N20°E 50.84'
Nail & Remon. tag 36" Maple	N75°E 112.2'	"X" cut in curb	N70°E 50.78'
Nail & Remon. tag 14" Maple	N35°E 94.64'	"X" cut in curb	N70°W 50.45'
Nail & Remon. tag 6" Elm	S40°W 36.78'	Iron	South 33'
C/L Tel. Ped. S07°W 33.9' and S42°E 43.1'		On C/L blacktop E-W & N	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Standard Kent County Monument	
Nail & KC Remon. tag E. side P. Pole	N35°W 63.46'
"X" cut on top concrete curb	N20°E 50.84'
"X" cut on top concrete curb	N70°E 50.78'
"X" cut on top concrete curb	N70°W 50.45'
On C/L blacktop E-W & N	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99