

RECORDATION

MAY 22 2000

KENT COUNTY REMONUMENTATION

Seg 2

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

Tyrone Twp.
F-12

1. Public Land Survey

T 10NR 12W

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

REG. OF DEEDS

1999 MAR 24 AM 8:02

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11157

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2			
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-12 1837	GLO	Whitcomb	Not Set
	Kent Co. Wits		Iron
1977	LCRC #1067	Merdzinski	3/4" Iron Pipe
1993	LCRC #6851	Chettleburgh	Set Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED

CHAIRMAN

2/25/99
[Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas M. Chettleburgh on 9-20-93 and was recorded per LCRC #6851.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas M. Chettleburgh in place of the Iron Pipe he found over a Stone. Said Iron Pipe & Stone check with Kent Co. Wit. and LCRC #1067.
LCRC #6851

Southwesterly gage railroad	N40°E	54.80'
Nail & Remon. tag N. side P. Pole	N85°E	159.59'
Nail & Remon. tag E. side 32" Maple	S10°E	125.28'
C/L Ball Creek Raod	S40°E	26.5'
Nail & Remon. tag S. side P. Pole	N78°W	219.57'
Nail & Remon. tag NE side P. Pole	N25°W	24.15'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-12 Standard Kent County Monument	N40°E	54.80'
Southwesterly gage railroad	N85°E	159.62'
Nail & KC Remon. tag S. side P. Pole	S10°E	125.33'
Nail & KC Remon. tag E. side 34" Maple	S40°E	26.5'
C/L Ball Creek Road	N78°W	219.57'
Nail & KC Remon. tag S. side P. Pole	N25°W	24.15'
Nail & KC Remon. tag NE side P. Pole		



Signed by

[Signature]

Surveyor's Michigan License No. 30077

Date

2/25/99