

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 JUL 14 AM 9:55

David J. Gland
REG. OF DEEDS

\$7.00
\$2.00

SECTION

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10</u> N R <u>12</u> W	F-13
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

10661

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13 1837 GLO	Brookfield	Set Post
1977 LCRC #1068	Merdzinski	1" Crimped Iron in Mon. Box
1980 LCRC #1486	Merdzinski	Set Kent County Monument in Mon. Box
1994 LCRC #7525	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/25/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 11-29-80 and was recorded per LCRC #1486.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with LCRC #1068.

LCRC #1486		LCRC #7525
RR Spike	East 16.84'	Nail & Remon. tag Twin Locust N85°E 36.71'
"X" on conc. culv.	N05°W 167.36'	Nail & Remon. tag wood fence post S08°E 119.79'
"X" on conc. culv.	N06°E 168.30'	Nail & Remon. tag P. Pole N50°E 50.64'
Nail & Remon. tag Tri. Locust	N85°E 36.72'	Nail & Remon. tag P. Pole N90°W 52.44'
Nail & Remon. tag C.P. Pole	S20°E 181.50'	Kent Co. Mon. (F-1, T9N, R12W) N90°E 16.86'
Edge of road is West 2.5'		Edge of road is West 1.5'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Standard Kent County Monument	
Nail & KC Remon. tag N. side Tw. 6" Locust	N85°E 36.75'
Nail & KC Remon. tag W. side 6" x 6" wood cor. fc. post	S08°E 119.79'
Nail & KC Remon. tag NW side P. Pole	N50°E 50.64'
Nail & KC Remon. tag S. side P. Pole	N90°W 52.44'
Kent Co. Mon. (F-1, T9N, R12W)	N90°E 16.88'
Edge of road is West 1.5' ±	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 6/25/98