

MAY 22 2000

37.00
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10</u> N R <u>12</u> W	Tyrone Twp. G-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 NOV -4 AM 8:37

11497

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 22, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-1	1837	GLO	Brookfield	Set Post
	1967	Kent Co. Wits		3/4" Iron in Mon. Box
	1985	LCRC #4373	Ochs	Set Kent County Monument on Twp. Line
	1994	LCRC #7539	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/23/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 10-23-85 and was recorded per LCRC #4373.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1	Found Kent County Monument (Harrison) per witnesses from above LCRC as set on Twp. Line by Norman L. Ochs in place of the 1" Iron he found. Said Iron checks with Kent Co. Wits.		
	LCRC #4373		
	LCRC #7539		
PK Nail P. Pole	N45°E 56.38'	Nail & Remon. tag P. Pole	N45°E 56.38'
PK Nail P. Pole	S30°E 86.21'	Nail & Remon. tag P. Pole	S30°E 86.21'
PK Nail P. Pole	S40°W 60.11'	Nail & Remon. tag P. Pole	S40°W 60.11'
Top MBT Riser	S45°E 57.27'	Top of MBT Riser	S45°E 57.27'
		S 1/4 cor. Sec. 34 Grant Twp.	N90°E 343.36'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1	Standard Kent County Monument
PK Nail NW side P. Pole	N45°E 56.40'
PK Nail E. side P. Pole	S30°E 86.21'
PK Nail NW side Guy Pole	S40°W 60.15'
Top of MBT Riser	S45°E 57.22'
S 1/4 cor. Sec34-11-12 (New. Co. Mon.)	East 343.17



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 10/28/99