

\$7.00
\$2.00

APR 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:52

REG. OF DEEDS

11158

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 12W	Tyrone Twp. G-2
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-2 1837	GLO	Whitcomb	Set Post
1915	Williams & Works		Iron & Stone
1967	Kent Co. Wits		1/2" Iron in Mon. Box
1986	LCRC #4453	Kolehouse	Set Kent County Monument in Mon. Box
1994	LCRC #7531	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Randy J. Kolehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 4-5-86 and was recorded per LCRC #4453.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 3/4" Iron he found inside a Mon. Box over a 1" Iron and Stone. All check with Williams & Works information and Kent Co. Wits.

LCRC #4453	Nail & Remon. tag P. Pole West 25.96'	LCRC #7531	Nail & Remon. tag West 25.96'
	SW cor. porch foundation N70°E 65.75'		SW corner porch foundation N70°E 65.65'
	NW cor. house foundation N45°E 87.0'		NW corner house foundation N50°E 86.90'
	Corner fence post East 28.3'		Nail & Remon. tag fence post N90°E 27.51'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 Standard Kent County Monument			
Nail & KC Remon. tag S. side Tel. Pole	West	25.96'	
SW corner concrete cap of porch	N70°E	65.74'	
NW corner house foundation	N50°E	86.85'	
Nail & KC Remon. tag S. side fence post	N90°E	27.51'	
Nail & KC Remon. tag E. side Tel. Pole	N10°W	171.61'	
Nail & KC Remon. tag E. side Tel. Pole	S15°W	147.20'	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/25/99