

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10</u> N R <u>12</u> W	Tyrone Twp. G-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

1999 MAR 24 AM 9:02

REG. OF DEEDS

[Signature]

11160

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 22, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9	●	10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4 1837	GLO	Whitcomb	Set Post
1925	Kent Co. Wits		3/4" Iron
1975	LCRC #825	Bonnema	3/4" Iron
1982	LCRC #2652	Jonker	Set Kent County Monument
1994	LCRC #7557	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 2-2-82 and was recorded per LCRC #2652.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Round Iron he found. Said Round Iron checks with LCRC #825 and Kent Co. Wits.

LCRC #2652		LCRC #7557
Capped Iron	N88°W 33.0'	Capped Iron N88°W 32.95'
Nail & Remon. tag 18" Oak clump	N85°W 23.64'	Nail & Remon. tag 24" Oak clump N85°W 23.68'
Nail & Remon. tag 16" Oak	N23°W 120.03'	Nail & Remon. tag 26" Oak N23°W 119.65'
Nail & Remon. tag 9" Oak	N03°E 213.0'	Nail & Remon. tag P. Pole N20°E 145.19'
Nail & Remon. tag 12" Oak	N80°E 168.77'	Nail & Remon. tag 6" x 6" wood post S66°E 41.43'
C/L B.T. East 3' m/l & on tree row to West		C/L B.T. East 3' m/l & on tree row to West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 Standard Kent County Monument	
Nail & KC Remon. tag S. side 24" Oak clump	N85°W 23.65'
Nail & KC Remon. tag SW side 30" Oak	N23°W 119.63'
Nail & KC Remon. tag W. side P. Pole	N20°E 145.12'
Nail & KC Remon. tag N. side 6" x 6" wood post	S66°E 41.51'
Nail & KC Remon. tag E. side P. Pole	S15°W 167.06'
C/L N-S asphalt road is 3' East ±	
On tree line to West	



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 2/25/99