

MAY 22 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00  
\$2.00

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
	Tyrone Twp.	
1. Public Land Survey	T 10N R 12W	G-12
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

1999 JUL -9 AM 11:20

REG. FEES

11254

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on June 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-12 1837	GLO	Whitcomb	Set Post
1961	Kent Co. Wits		3/4" Iron
1977	LCRC #1068	Merdzinski	"T" Iron over 1/2" Iron
1983	LCRC #3425	Bueche	Set Kent County Monument
1991	LCRC #7567	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/24/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 5-18-83 and was recorded per LCRC #3425.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 Established location of corner and set Kent Co. Mon. in Mon. Box in newly paved road per witnesses from above LCRC as set in 1983 by John C. Bueche in place of the "T" Iron over a Round Iron & Stone he found. Said checks with Kent Co. Wits. and LCRC #1068.

LCRC #3425	LCRC #7567
Nail & Remon. tag P. Pole N10°E 45.55'	Nail & Remon. tag P. Pole N10°E 45.60'
Nail & Remon. tag P. Pole N75°E 156.98'	Nail & Remon. tag P. Pole N75°E 157.08'
"V" on CMP S70°W 46.05'	"V" cut on NE tower leg S55°E 73.22'
"V" cut on tower leg S55°E 73.22' & S40°E 71.64'	"V" cut on SW tower leg S40°E 71.64'
Top C/L steel fence post N65°E 74.23'	Top C/L steel fence post N65°E 75.25'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 Standard Kent County Monument in Mon. Box

Nail & KC Remon. tag E. side P. Pole	N10°E	45.60'
Nail & KC Remon. tag S. side P. Pole	N75°E	157.03'
"V" cut on NE leg of tower (3' high)	S55°E	73.22'
"V" cut on SW leg of tower (3' high)	S40°E	71.61'

C/L N-S power lines are 55' ± East  
On C/L blacktop road E-W ±



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 6/24/99