

SECTION
 24 2533

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 1999 DEC 15 AM 8:57
 REG. OF DEEDS

For corners in

KENT COUNTY
 (County)

Located In:	Corner Code #
T 10N R 12W	Tyrone Twp. H-8
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

11609

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Oct. 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-8 1837 GLO Not Set
- 1896-1912 Williams & Works Stone
- 10" B. Oak SE 65' 20" W.P. stump SE 42' 30" W.P. stump 49'
- 1934 Kent Co. Wits Stone
- 6" Elm NE 31' 4" Poplar SSE 51.75' 6" Box Elder W 29.0'
- 1975 Survey J. Clapp Set Steel Bar per 2 previous witnesses
- 12" Poplar SSE 51.30' C/L Elm stump NE 31' 8" Ash NW 37.60' 15" Maple SW 28.85' PP East 116.70'
- 1983 LCRC #3702 Hay Found Steel Bar - set by J. Clapp
- 14" Maple S50°W 28.87' 10" B. Elder N45°W 37.54' Iron East 33'

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 10/28/99
 CHAIRMAN Harry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-8 Found Rerod and Broken Cap inside an Iron Pipe per the following remaining witnesses:
 Fd. Nail NW side 20" Maple S50°W 28.84' Iron Pipe East 33.03'

Said Rerod inside Iron Pipe is 0.5' East and 0.5' South of Intersection of 1/4 lines and agrees ± with measurements of Clapp, Hay, Roosien and Nederveld.

The Rerod with Broken Cap inside an Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-8 Set Standard Kent County Monument in place of the Rerod with Broken Cap and Iron Pipe
- Nail & tag NW side 20" Maple S50°W 28.84'
- Nail & tag NE side P. Pole N25°W 78.98'
- 1" Iron Pipe East 33.03'
- Nail & KC Remon. tag N. side 6" Poplar S75°E 25.23'
- Nail & KC Remon. tag SW side 12" Poplar S45°E 60.68'



Signed by Kirk Breitels
 Surveyor's Michigan License No. 30077

Date 12/6/99