

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CORNER RECORDATION
 RECEIVED
 93 SEP -9 7:12:00

For corners in

Kent

(County)

Located In:

Corner Code 11

1. Public Land Survey

T 10N R 12W

H-10

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____

Recorded Plat _____

5. Private Claims _____

6841

Register of Deeds Stamp & File Number

I, Wallace E. Glaza, in a field survey on July 30, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No previous history.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10 (Center of Section 27, T10N, R12W, Tyrone Township, Kent County, Michigan)

Found MUK iron. Verified iron to be at the intersection of the $\frac{1}{4}$ lines.
 Accepted iron as center.

Replaced MUK iron with standard 4" x 30" Harrison Monument.

South $\frac{1}{4}$ corner to center - 2667.84'

West $\frac{1}{4}$ corner to center - 2638.50'

North $\frac{1}{4}$ corner to center - 2669.51'

East $\frac{1}{4}$ corner to center - 2635.84'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10 (Standard 4" x 30" Harrison Monument)

1) Nail and tag in W side 22" Maple N07°E 431.34'

2) Nail and tag in N side power pole S88°E 211.73'

3) Nail and tag in W side 24" Locust S10°E 295.39'

4) West edge of bituminous road East 7.8'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		1		15		36		
13													



Signed by Wallace E. Glaza
 Glaza and Associates, Inc.
 Surveyor's Michigan License No. 31592

Date Sept 1, 1993