

MAY 22 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

SECTION

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
	Tyrone Twp.	
1. Public Land Survey	T 10N R 12W	I-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 NOV -4 AM 8:37

11501

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 23, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-1	1837	GLO	Brookfield	Set Post
		Kent Co. Wits		1/2" Iron in Mon. Box
	1985	LCRC #4375	Ochs	Set Kent County Monument on Twp. Line
	1991	LCRC #6002	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/23/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 10-23-85 and was recorded per LCRC #4375.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1	Found Kent County Monument (Harrison) per witnesses from above LCRC as set on Twp. Line by Norman L. Ochs.		
	1/2" Iron Pipe found per Kent Co. Wits. was 4.86' South of Twp. Line.		
	LCRC #4375		
	LCRC #6002		
Nail in P. Pole	S30°W 38.18'	Nail & Remon. tag P. Pole	S30°W 38.04'
Spike in P. Pole	N45°E 57.26'	Nail & Remon. tag P. Pole	N45°E 57.23'
Nail in 15" Maple	S35°E 42.05'	Nail & Remon. tag 18" Maple	S35°E 42.03'
Nail & Remon. tag 26" Pine North	61.67'	Nail & Remon. tag 44" Maple	N25°W 58.58'
S 1/4 Grant Twp.	West 331.56'	SW corner house foundation	N35°W 109.67'
		Cast iron Mon. (S1/4 cor. Sec.35-11-12)	N90°E 331.56'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1	Standard Kent County Monument
Nail & KC Remon. tag E. side P. Pole	S30°W 38.09'
Nail & KC Remon. tag E. side P. Pole	N45°E 57.23'
Nail & KC Remon. tag E. side 20" Maple	S35°E 42.03'
Nail & KC Remon. tag E. side 46" Maple	N25°W 58.58'
SW corner house foundation	N35°W 109.67'
S 1/4 cor. Sec. 35-11-12 (New. Co. Mon.)	East 331.63'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 10/28/99