

\$7.00
\$2.00

MAY 28 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 9:02

REG. OF DEEDS

11175

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey

T10N R 12W

I-8

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-8	1837	GLO	Whitcomb	Set Post
		Kent Co. Wits		Iron & Stone
	1983	LCRC #3702	Hay	Iron
	1984	LCRC #3884	Kolehouse	Set Kent County Monument
	1991	LCRC #6009	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Randy J. Kolehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 8-11-84 and was recorded per LCRC #3884.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8	Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 3/4" Iron in top of a 1" Iron he found. Both Irons check with Kent Co. Wits. and LCRC #3702.			
	LCRC #3884	LCRC #6009		
	Nail & Remon. tag 18" Ash	N10°E 17.04'	Nail & Remon. tag 24" Ash	N10°E 17.00'
	Nail & Remon. tag 10" Ash	N30°W 12.80'	Nail & Remon. tag 12" Ash	N30°W 12.70'
	Nail & Remon. tag Tw. 8" Birch	S45°W 17.15'	Nail & Remon. tag Tw. 8" Birch	S45°W 17.27'
	Nail & Remon. tag fence post	South 5.2'	Nail & Remon. tag fence post	S00°W 5.39'
	Nail & Remon. tag		Nail & Remon. tag 8" Birch	S25°E 26.47'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8	Standard Kent County Monument	
	Nail & KC Remon. tag W. side 27" Ash	N10°E 16.97'
	Nail & KC Remon. tag E. side 15" Ash	N30°W 12.60'
	Nail & KC Remon. tag N. side Tw. 10" Birch	S45°W 17.27'
	Nail & KC Remon. tag NE side 10" Birch	S25°E 26.47'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/25/99