

\$7.00  
\$2.00

MAY 28 2000

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:02

REG. OF DEEDS

11178

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey	T10N R 12W	I-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-11 1837	GLO	Whitcomb	Set Post
1966	Kent Co. Wits		Iron on Stone
1972	LCRC #142	N.C. Jones	Conc. Mon. in Mon. Box
1983	LCRC #3431	Bueche	Set Kent County Monument in Mon. Box
1991	LCRC #6012	Byl	Kent County Monument in Mon. Box
1995	LCRC #8750	Breitels	Reset Kent County Monument in Mon. Box after construction

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 5-18-83 and was recorded per LCRC #3431.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as reset by Kirk Breitels in the same location as set by John C. Bueche in place of the 1" Rerod and Conc. Mon. he found inside a Mon. Box. Both Rerod and Conc. Mon. check with Kent Co. Wits. and LCRC #142.

LCRC #3431		LCRC #6012 - #8750	
Nail & MSHD tag P. Pole	S40°W 67.88'	Nail & MSHD tag P. Pole	S40°W 67.88' - 67.87'
PK Nail P. Pole	N35°W 55.67'	PK Nail P. Pole	N35°W 55.97' - 55.67' (Nail & Remon. tag)
Nail & Remon. tag Guy Pole	S65°E 102.63'	Nail & Remon. tag Guy Pole	S65°E 102.60' - 102.63'
SW corner frame building	N45°E 134.50'	SW corner frame building	N45°E 134.50' - 134.50'
NW corner frame building	S25°E 153.17'	NW corner frame building	S25°E 153.26' - 153.17'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Standard Kent County Monument in Mon. Box

Nail & MSHD tag SE side P. Pole	S40°W	67.87'
Nail & KC Remon. tag E. side P. Pole	N35°W	55.67'
Nail & KC Remon. tag N. side Guy Pole	S65°E	102.63'
SW corner frame building	N45°E	134.50'
NW corner frame building	S25°E	153.17'



Signed by *[Signature]*  
Surveyor's Michigan License No. 30077

Date 2/25/99