

\$7.00  
\$2.00  
SURVEY &  
REMONUMENTATION

KENT COUNTY REMONUMENTATION

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY SECTION  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R12W I-13  
T R  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13	1837	GLO	Brookfield	Set Post
	1947	Kent Co. Wits		1 1/2" Iron
	1972	LCRC #159	Bonnema	"T" Iron
	1980	LCRC #1501	Merdzinski	Set Kent County Monument
	1991	LCRC #6014	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN Nancy Dupere

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 12-9-80 and was recorded per LCRC#1501.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Wagon Wheel Hub he found. Said Wagon Wheel Hub checks with Kent Co. Wits. and LCRC #159.

LCRC #1501		LCRC #6014	
Nail & Remon. tag P. Pole	S10°W 86.10'	Nail & Remon. tag P. Pole	S10°W 86.00'
Nail & Remon. tag 10" Elm	N15°W 37.60'	"X" cut on conc. culv.	S80°W 19.67'
Nail & Remon. tag fence post	N80°W 25.96'	Kent Co. Mon (NW cor. 2-9-12)	N90°E 60.56'
Nail & Remon. tag fence post	N45°W 34.98'	Nail & Remon. tag P. Pole	N15°W 101.49'
"X" cut on conc. culv.	S80°W 19.67'	Nail & Remon. tag 12" Poplar	N60°E 122.98'
"T" Iron in Mon. Box	N90°E 60.53'	Nail & Remon. tag 10" Elm	S50°E 141.91'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Standard Kent County Monument	
Nail & KC Remon. tag E. side P. Pole	S10°W 85.94'
"X" cut on concrete culvert	S80°W 19.67'
Nail & KC Remon. tag W. side P. Pole	N15°W 101.49'
Nail & KC Remon. tag SE side 12" Poplar	N60°E 123.08'
Nail & KC Remon. tag SW side 14" Elm	S50°E 141.95'
Nail & KC Remon. tag S. side 14" Elm	S70°E 134.42'
Kent Co. Mon. (I-1, T9N, R12W)	N90°E 60.60'
20' ± West of West edge asphalt road N-S	



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

98 MAR -5 AM 8:31

REG. OF DEEDS

L. J. Boyd

10507  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	10			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													