

MAY 23 2530

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

Tyrone Twp.

1. Public Land Survey

T 10N R 12W

J-3

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitel, in a field survey on May 25, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-3	1837	GLO	Whitcomb	Set Post
	1906	Williams & Works		Found Stake - set new Stake - property owner to set Stone
	1991	LCRC #5861	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 5-13-91 and was recorded per LCRC #5861.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche by single proportionate measure - did not find Stake or Stone. Location agrees ± with Williams & Works measurements. LCRC #5861

- Nail & Remon. tag S. side Twin 12" Ash N75°E 7.74'
- Nail & Remon. tag W. side 8" Ash S50°E 44.25'
- Nail & Remon. tag E. side 8" Ash S15°W 42.75'
- Nail & Remon. tag E. side 6" Cedar N45°W 48.05'
- Nail & Remon. tag E. side 4" Cedar N05°W 56.08'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/24/99
CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-3 Standard Kent County Monument in swamp
- Nail & KC Remon. tag S: side dead Twin 12" Ash N75°E 7.74'
- Nail & KC Remon. tag W. side 8" Ash S60°E 44.25'
- Nail & KC Remon. tag E. side dead 8" Ash S15°W 42.75'
- Nail & KC Remon. tag E. side 6" Cedar N45°W 48.05'
- Nail & KC Remon. tag E. side 6" Cedar N05°W 56.13'



Signed by *Kirk Breitel*
Surveyor's Michigan License No. 30077

Date 6/24/99