

\$7.00
\$2.00

MAY 28 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
KENT COUNTY
(County)

Located In: Corner Code #
Tyrone Twp.
J-6

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

	T	R	12W	
	T	R		
	T	R		
	T	R		
S	T	R		
S	T	R		
S	T	R		
S	T	R		

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 17 AM 8:01
REG. OF DEEDS

11625

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Dec. 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-6 1837 GLO
Williams & Works
Kent Co. Wits

Not Set
No information
No information

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/02/99
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-6 Established Intersection of 1/4 lines and found nothing. Location falls in a wet grassy area.

Intersection of 1/4 lines fits computed dimensions of surveys by Roosien and Glaza.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-6 Set 3/4" x 9' Iron Pipe with yellow "Kent Co. Remon." cap at the Intersection of 1/4 lines.

Nail & KC Remon. tag W. side 14" dead tree N35°W 27.25'

Nail & KC Remon. tag N. side 12" Ash N60°E 94.71'

Nail & KC Remon. tag E. side 6" Maple S40°E 62.03'

Nail & KC Remon. tag SE side 40" Oak S45°W 148.13'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 12/15/99