

\$7.00  
\$2.00

357 64 2059

# KENT COUNTY REMONUMENTATION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
	Tyrone Twp.	J-9
1. Public Land Survey	T <u>10</u> R <u>12</u> W	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

1999 MAR 24 AM 8:03

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

11182

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 19, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9	1837	GLO	Whitcomb	Set Post
		Kent Co. Wits		Mon. Box
	1972	LCRC #192	Salisbury	Iron in Mon. Box
	1982	LCRC #2958		Iron in Mon. Box
	1982	LCRC #3127	Merdzinski	Set Kent County Monument
	1991	LCRC #6018	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 2/25/99  
 CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10-5-82 and was recorded per LCRC #3127.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Iron over a Conc. Mon. in a Mon. Box that he found. All check with Kent Co. Wit. and LCRC's #192 & #2958.

LCRC #3127	Nail & Remon. tag P. Pole	N45°W 49.08'	LCRC #6018	Nail & Remon. tag P. Pole	N45°W 49.08'
	Nail & Remon. tag 6" Ash	N07°W 53.74'		Nail & Remon. tag 8" Ash	N07°W 53.74'
	Nail & Remon. tag 12" Elm	S15°W 93.15'		Nail & Remon. tag 16" Elm	S15°W 93.00'
	Nail & Remon. tag in curb joint	S45°E 36.35'		Nail & Remon. tag in curb joint	S45°E 36.35'
	On C/L of E-W road			Nail & Remon. tag in curb joint	S45°W 35.89'
	Road to South is 3' East				

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Standard Kent County Monument

Nail & KC Remon. tag NE side P. Pole	N45°W 49.12'
Nail & KC Remon. tag W. side 36" Maple	N05°W 83.65'
Nail & KC Remon. tag in curb joint	S45°E 36.52'
Nail & KC Remon. tag in curb joint	S45°W 36.01'
On C/L E-W road	
C/L road to South is 3' East	



Signed by Kirk Breitels  
 Surveyor's Michigan License No. 30077

Date 2/25/99